

ASTHIWAR DESIGN & BUILD

Turnkey Residential Construction & Civil Engineering • Tamil Nadu
Coimbatore • Chennai • Tiruppur • Erode • Pollachi • Madurai | Web: asthiwar.com

OFFICIAL QUOTATION

EST-2026-916207

Generated: 03 Sept 2026

CLIENT INFORMATION

Customer Name: test1
Contact Phone: 9098765432
Email Address: test@gmail.com

PROJECT SPECIFICATIONS

Plot Location: Coimbatore
Floors & Plot: G+1 • Plot: 2400.00 Sq.Ft
Total Built-Up: 3,200 Sq.Ft

1. PACKAGE & BASE CONSTRUCTION COST

Selected Package Tier	Total Built-up Area	Effective Rate / Sq.Ft	Base Amount (INR)
STANDARD PACKAGE	3,200 Sq.Ft	Rs. 2,468 / sq.ft	Rs. 78,97,600

2. BRAND CUSTOMIZATIONS & SPECIFICATION UPGRADES

Item Category	Selected Brand / Option	Rate Delta	Amount Addition
Steel Rebar Fe 550D & Binding Wires	SPA / Vizag Steel & TATA Wire	Included	Rs. 0
Cement	JSW Cement	Included	Rs. 0
Masonry Work	Fly Ash / AAC Blocks	Included	Rs. 0
Basement Height (from ground level)	Fly Ash Bricks upto 3 ft (Std)	Included	Rs. 0
Ceiling Height	10 ft Ceiling Height (Std)	Included	Rs. 0
Water Proofing & Basement PCC	PCC + Dr.Fixit/Fosroc/Bostik Waterproofing	Included	Rs. 0
Soil Testing	Soil Testing (Not Included - Std)	Included	Rs. 0
Electrical & Plumbing Drawings	MEP Drawings (Not Included - Std)	Included	Rs. 0
Isometric Views & Virtual Reality	Isometric Views & VR (Not Included - Std)	Included	Rs. 0
Kitchen Wall Tiles & Kitchen Countertop	4 ft Tiles + Granite Slab upto 15 rft	Included	Rs. 0
Wall Tiles	7 ft coverage @ Rs. 45/sq.ft	Included	Rs. 0
Sanitary & CP Fittings	Parryware (Rs. 20,000/bath allowance)	Included	Rs. 0
PVC and CPVC Pipes	Watertec Pipes	Included	Rs. 0
Main Flooring, Balcony Tiles	4'x2' Main (Rs. 50/sqft) + 2'x2' Balcony (Rs. 50/sqft)	Included	Rs. 0
Staircase	2'x2' Tiles @ Rs. 50/sq.ft	Included	Rs. 0
Parking	Tiles @ Rs. 50/sq.ft	Included	Rs. 0
Main Door & Internal Doors	Readymade Teak 5"x4" + Laminated Flush Doors	Included	Rs. 0
Balcony & Headroom Doors	Flush Door, Sal/Mahogany Frame (Std)	Included	Rs. 0
Bathroom Doors	WPC Doors	Included	Rs. 0
PAINTING	2 JSW Putty + Asian Primer + Tractor/Ace Emulsion	Included	Rs. 0
Wires, Switches & Pipes	RR/Orbit Wires + Anchor Roma + Anchor/Finolex Pipes	Included	Rs. 0
Lights	Luker Lights	Included	Rs. 0
Staircase and Balcony Railings	MS Railings (Std)	Included	Rs. 0
Parapet Wall (if headroom is built)	3 ft - 4.5" thick (Std)	Included	Rs. 0

3. SELECTED ADD-ONS & INFRASTRUCTURE

Add-On Name	Variant / Specification	Quantity / Unit	Total Cost
Motor Automation (Auto Cut-Off)	BOTH (BORE & CORPORATION WATER OHT)	1 fixed	Rs. 24,000

Base Construction Cost: Rs. 78,97,600

Add-Ons Subtotal: Rs. 24,000

TOTAL PROJECT COST: Rs. 79,21,600

10-STAGE CIVIL MILESTONE PAYMENT SCHEDULE

Payments are strictly linked to on-site civil completion stages with zero front-loading. Each stage requires engineer sign-off:

Stage	Milestone Description & Work Scope		Share %	Amount (INR)
Stage 1	Design & Approvals	Soil test, floor plan, structural drawing, DTCP approval assistance	3%	Rs. 2,37,648
Stage 2	Earthwork & Excavation	Foundation trenching, site leveling, anti-termite treatment	4%	Rs. 3,16,864
Stage 3	Foundation & Plinth	Footing concrete, plinth beam, basement filling, PCC/RCC basement	15%	Rs. 11,88,240
Stage 4	RCC Structure (Columns & Slabs)	Column casting, roof slab shuttering, beam reinforcement & curing	22%	Rs. 17,42,752
Stage 5	Brickwork & Masonry	External & internal walls, lintels, parapet wall construction	14%	Rs. 11,09,024
Stage 6	Electrical & Plumbing Concealing	Conduits, plumbing lines, switch boxes, drainage routing	8%	Rs. 6,33,728
Stage 7	Plastering (Internal & External)	Ceiling plastering, wall leveling, exterior weather-coat plaster	10%	Rs. 7,92,160
Stage 8	Flooring & Wall Tiling	Main vitrified tiles, bathroom tiling, kitchen granite countertop	11%	Rs. 8,71,376
Stage 9	Painting & Woodwork	Putty, primer, emulsion coats, main door & internal door fixing	8%	Rs. 6,33,728
Stage 10	Fixtures, Finishing & Handover	CP & sanitary fittings, switches, lights, glass railings, deep clean	5%	Rs. 3,96,080
TOTAL CONTRACT VALUE			100.00%	Rs. 79,21,600

TERMS & STANDARD CONDITIONS

- Quotation Validity: This estimate is valid for 30 calendar days from the date of generation.
- Rate Basis: Built-up area is calculated outer-to-outer including balconies and parking as specified.
- Standard Inclusions: 100% material, labor, structural drawings, 3D elevation, site engineer supervision.
- Standard Exclusions: Government building approval fees, EB permanent connection deposits, borewell depth beyond allowances.
- Payment Guarantee: Zero advance beyond Stage 1 booking fee; milestone payments only upon site stage verification.

STANDARD EXCLUSIONS & CLIENT SCOPE (Out of Scope for Civil Contract):

- Elevation Work (Special exterior stone/HPL claddings)
 - Outer Area Development (Setbacks, paving & landscape)
 - Interior Works & Carpentry (Wardrobes, modular units)
 - DTCP & Local Body Building Plan Sanction Fees
 - Electricity Board (EB) Connection & Meter Deposits
 - Gas Connection & Piped Gas Installation Charges
- Drinking Water & Drainage (UGD) Connection Fees
 - Borewell Drilling, Casing & Submersible Piping
 - Water Pumps & Motors (unless chosen as Add-On)
 - Electrical Appliances (TV, Fridge, ACs, Chimney)
 - Vacant Land Tax (VLT) & Local Property Taxes

For Asthiwar Design & Build
Authorized Engineering Signatory

Customer Acknowledgment
Signature / Acceptance Date: